

Date: January 13, 2024

Institution: Clan Carthy High School

Address: Kingston

To: Karim Turner HOD

Comprehensive Repair Estimates for Woodwork Machines

Estimate to include:

- Travel to the machine's location.
- Identifying machines for repairs.
- Identifying parts and accessories needed to facilitate repairs.
- Prepare and submit estimates.
- Supply and install parts and accessories.
- Complete realignment and calibration of machines etc.
- Deoxidation of machines/tool services (Optional).

Please note that this project may incur additional costs, and any additional costs incurred will be added to the final invoice upon the satisfactory completion of the project. Please note that portable tools repair if applicable will be added to a separate invoice upon completion of project.

50% of the estimated repair cost is required at the start of each project.

The 50% deposit needed to start this project is

\$463,189.00

Please note cheques must be made out to company
'Seaton's machines, allied repair & trade solutions ltd'

Estimated time of completion **24 days**



Gavin Seaton (Operations Manager)

TRN 002790572

S.M.A.R.T

SEATON'S MACHINES, ALLIED REPAIR AND TRADE
SOLUTIONS LTD

25 1/2 Chisholm Avenue,
Kingston 13, Jamaica.
info@smartsja.com
(876) 580-8151 / (876) 863-2341

(1) One 110v 1'5hp x 14" x93 1/2" Band Saw.		
Observation/Inspection	Actions to be taken	Cost
	(a) Repair flywheel assembly to include; two (2) new upper and lower tires. (b) Supply and install new 93 1/2" blade. (c)Regulate motor speed ratio assembly. (d) Repair bottom friction guide assembly	\$176, 478.00
(2) One 1'5hp x 1/2" Drill Press		
Observation/Inspection	Actions Taken	Cost
	(a)Repair/Replace defective Isolator switch. (b) Replace/Repair chuck & key assembly (c) Repair elevating table assembly	\$117, 380.00
(3) One 36" Wood Lathe		
Observation/Inspection	Actions Taken	Cost
	(a) Service tool post assembly (b) Adjust tail stock cam mechanisms	\$41, 350.00
(4) One 220v 3ph 15a x 5hp x 10" Circular Saw		
Observation/Inspection	Actions Taken	Cost
	(a) Modify motor bracket assembly (b) Supply and install new 3ph x 15a x 5hp starter switch (c) Supply and install two (2) double groove pulleys a p r. (d) Service trunion assembly	\$353 ,670.00
(5) One 110v 1ph x6" Jointer		
Observation/Inspection	Actions Taken	Cost
	(a) remove repair and re install one 2'5hp motor (b)remove, sharpen and re install one set 3x14 cutter blade (c) Supply and install start switch. (d) Supply and install isolator switch	\$237, 500.00

Woodwork project estimate \$926,378.00

S.M.A.R.T

SEATON'S MACHINES, ALLIED REPAIR AND TRADE
SOLUTIONS LTD

25 1/2 Chisholm Avenue,
Kingston 13, Jamaica.
info@smartsja.com
(876) 580-8151 / (876) 863-2341

BANKING INFO

Seatons Machines Allied Repair and Trade Solutions Ltd.

Bank: CIBC (First Caribbean Bank)

Branch: Portmore

Account number: 1002259000

Account type: Chequing account

Please note cheques must be made out to company
'**Seaton's machines, allied repair & trade solutions ltd**'